BRUHAT BANGALORE MAHANAGARA PALIKE

Repairing work Range office Building, removal of debries and providing new precast RCC covering slabs desilting of drains in ward no.12 Shettyhalli

JOB Code:- Est Cost 35.25 Lakhs

Sl No	Description	Unit	No	Length	Width	Depth	Qty	Rate	Amount
1	Providing skilled labour (mazdoor Heavy)for removal of debris, slabs resetting,desilting of drains and other ward maintainence works. (Pg No -LVI, & Itm No 5) (160) (b)							451.22 45.1 496.32	
	3Months (90 Days) X 10 Nos	Day	90	12.00			1080.00		
							1080.00	**446.20**	**481896.00**
	Basic Rate	446.20							
2	Hire charges of **Tractor 40HP** including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.19)								
		Day	90	1.00			90.00		
							90.00	**1128.00**	**101520.00**
	Basic Rate	1128.00							
3	Hire charges of **JCB excavator** including cost of driver, Fuel and other incidental charges. (Pg No-XLVIII, Sl. No.23)								
		Day	120	1.00			120.00		
							120.00	**5695.00**	**683400.00**
	Basic Rate	5695.00							
4	Removing and Re Setting of Footpath slabs (PWD SR 2018-19 P.No: 270, I.No.: 37.56)								
	Drain Cover slabs	**Sqm**	1	400.00	0.90		360.00		
							360.00		
	Desduction 15% Damage & Missing Slabs			25%			90.00		
							450.00	**208.82**	**93969.00**
	Basic Rate	197.00							
	Add 6% Area weightage	11.82							
	Total	**208.82**							
5	Providing and laying 25cm thick Pre Cast Cover slabs including cost of all materials, labours, curing, transportation, loding unloding etc.., complete as per the direction of Engineer in charge.								
		Sqm	20	1.50	0.60		18.00		
							18.00	**5418.00**	**97524.00**
	Data Rate	**5418.00**							
6	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge (Data Rate)								
	Missing & Damage Slabs For Drain		204	0.60	0.90		110.16		
		Sqm					**110.16**	2337.00	**257444.00**

Sl No	Description	Unit	No	Length	Width	Depth	Qty	Rate	Amount
	Data Rate	2337.00							
7	Providmg SS pipe name boards-made of 2" (65mm) dia SS pipe for vertical pole and 3no of horizontal support pipe of 11/2" dia. pipe each of length 1.00 mtr sinage board of size 60x45cm and 60x23cm size made of 16 guage SS sheet welded to SS tube frame of size 25x25 mm all manual are cut size and all items electricals welded as per the drawing all Joints are grainded smooth and pasted along with the sticker printed the name of the road and name of the elected mambers fixed to ground in 1 : 2 :4 with PCC at the bottom, all cost inclusive of lead a nd lifts Chapter, 530.0								
	Main and Cross roads	No	58				58		
		Data Rate	22342.96				58	22342.96	1295892.00
								SUB TOTAL	3011645.00
								GST 12%	361397.40
								Add Tender Primium charges @ 5%	150582.25
								Micelleneous and rounding off	1375.35
								TOTAL	3525000.00

ದೃಢೀಕರಣ

1. ಸದರಿ ಅಂದಾಜು ಪಟ್ಟಿಯಲ್ಲಿ ಪ್ರಸ್ತಾಪಿಸಿರುವ ರಸ್ತೆಗಳ ಅಭಿವೃದ್ಧಿ ಈ ಹಿಂದೆ ಯಾವುದೇ ಅನುದಾನದಲ್ಲಿ ಪ್ರಸ್ತಾಪಿಸಿರುವುದಿಲ್ಲ. ಹಾಗೂ ಪುನರಾವರ್ತನೆಯಾಗಿರುವುದಿಲ್ಲ ಎಂದು ದೃಢೀಕರಿಸಿದೆ.
2. ಸದರಿ ಪ್ರಸ್ತಾಪಿಸಿರುವ ರಸ್ತೆಗಳು DLP ಅವಧಿಯಲ್ಲಿರುವ ರಸ್ತೆಗಳಲ್ಲಿ ಸೇರಿರುವುದಿಲ್ಲ.
3. ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ಪಿ.ಡಬ್ಲ್ಯೂ.ಡಿ ಎಸ್.ಆರ್–2018–19ನೇ ಸಾಲಿನ ದರಗಳನ್ವಯ ತಯಾರಿಸಲಾಗಿದೆ ಹಾಗೂ Approved Data Rate ಅನ್ವಯ ತಯಾರಿಸಲಾಗಿದೆ.
4. ಸದರಿ ಕಾಮಗಾರಿಯಲ್ಲಿ ಪ್ರಸ್ತಾಪಿಸಿರುವ ರಸ್ತೆಗಳ ಅಭಿವೃದ್ಧಿಯು ತುಂಬಾ ಅವಶ್ಯಕವಾಗಿರುತ್ತದೆ.
5. ಎಲ್ಲಾ ರಸ್ತೆಗಳು ಬಿಬಿಎಂಪಿಯ ಸರಹದ್ದಿನಲ್ಲಿರುತ್ತದೆ.

Assistant Engineer
Ward No 12

Assistant Executive Engineer
Shetty Halli Sub Division

Executive Engineer
Dasarahalli Division

ADMINISTRATIVELY SANCTIONED FOR
(Rupees Thirty Five lakh Twenty Five thousand only P- 3726
Under the Head of Account
Registered as no EE(D.D.)/AS 180 Subject
conditions contained in Enclosed Memo
FE/DD/AS/180/21-22 Dt: 13/01/22
Exe. Eng
DASARAHALLI) BBMP

Technically Sanctione for Rs. 35.25 lakhs
Rs. In words Rs. Thirty Five lakhs Thirty five thousand and
Under
12-3726
Job Code No.
Registered as CE No. 109/21-22 Subject
conditions contained in Enclosed Memo
No. CE/DA/TS/109/21-22 Dt: 14/01/2022